



Winning with Green Remediation Practices at the Former McClellan AFB, Sacramento CA

**Mr. Steve Mayer, PMP, P.E.
McClellan Remediation Program Manger
Air Force Real Property Agency**

May 12, 2011



Report Documentation Page				Form Approved OMB No. 0704-0188	
Public reporting burden for the collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to a penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.					
1. REPORT DATE 12 MAY 2011		2. REPORT TYPE		3. DATES COVERED 00-00-2011 to 00-00-2011	
4. TITLE AND SUBTITLE Winning with Green Remediation Practices at the Former McClellan AFB, Sacramento CA				5a. CONTRACT NUMBER	
				5b. GRANT NUMBER	
				5c. PROGRAM ELEMENT NUMBER	
6. AUTHOR(S)				5d. PROJECT NUMBER	
				5e. TASK NUMBER	
				5f. WORK UNIT NUMBER	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) Air Force Real Property Agency, 2261 Hughes Ave., Suite 121, Lackland AFB, TX, 78236-9821				8. PERFORMING ORGANIZATION REPORT NUMBER	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)				10. SPONSOR/MONITOR'S ACRONYM(S)	
				11. SPONSOR/MONITOR'S REPORT NUMBER(S)	
12. DISTRIBUTION/AVAILABILITY STATEMENT Approved for public release; distribution unlimited					
13. SUPPLEMENTARY NOTES Presented at the NDIA Environment, Energy Security & Sustainability (E2S2) Symposium & Exhibition held 9-12 May 2011 in New Orleans, LA.					
14. ABSTRACT					
15. SUBJECT TERMS					
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT Same as Report (SAR)	18. NUMBER OF PAGES 19	19a. NAME OF RESPONSIBLE PERSON
a. REPORT unclassified	b. ABSTRACT unclassified	c. THIS PAGE unclassified			



Overview


- McClellan History
- Remediation Programs
 - Groundwater
 - Soil vapor extraction
 - Fuels bioventing
 - Soil Cleanup
- Right Sizing
 - Reduces environmental impacts
 - Reduces energy demands
 - Increases sustainability
 - Saves taxpayers' money



Location and History



- McClellan was a large, industrial city
 - Sept. 1936 base opened
 - 1995 BRAC listed
 - July 2001 base closed



McClellan History



- McClellan's mission was repair depot and system management
 - Aircraft
 - Communications
 - Electronics
 - Space
- 1979 groundwater contamination discovered
- 1987 placed on EPA National Priorities List





Background

- Extensive soil and groundwater contamination
 - Primarily solvents (TCE, PCE)
 - Metals (lead, cadmium, chromium)
 - Fuels (gas and diesel)
 - Radiological (Radium 226)
- Largest cleanup effort in the Air Force
 - 318 sites
- Interbedded (sand, silt, clay) geology presents challenges (low permeability)
- BRAC cleanup Team
 - Air Force
 - EPA Region IX
 - State of California



Remediation Programs



- Groundwater
- Soil vapor extraction
- Fuels bioventing
- Soil


“Right sizing” of programs has resulted in green successes in all four



Groundwater Cleanup



- 100 extraction wells
- 500 monitoring wells
- Approximately 1,450 gallons per minute
- More than 65,000 lbs of VOCs removed from 16 billion gallons of water



Right Sizing Groundwater Treatment



- Implemented air stripping alone as treatment for meeting de minimus VOC discharge standards (<2 lbs/day)
 - Eliminated energy-intensive thermal processes
 - Eliminated liquid-phase granular activated carbon (LGAC) to polish air stripper effluent
- Reduced overall carbon footprint
 - LGAC backwash
 - Carbon reactivation

□ Saves more than \$200,000/year in utility costs



Right Sizing Groundwater Treatment



- Eliminated satellite groundwater treatment system
 - Air stripper pre-treated hot spot before transporting water to main GWTP
 - As VOC concentrations were reduced, system became redundant
 - Reduced greenhouse gas production and realized energy savings of \$40,000/yr.



Right Sizing Groundwater Treatment



- Downsized hexavalent chromium ion exchange treatment system in 2009
 - Replaced two 500-cubic-foot resin vessels with one 60-cubic-foot resin vessel
 - Eliminates excess resin regeneration
 - Saves more than \$100,000 per year in decreased utility costs, resin subcontractor costs, and disposal fees



Right Sizing Groundwater Treatment



- Sampling
 - Converting from purge and bail to passive Hydrasleeve
 - Eliminates purge water generation
 - Eliminates onsite pump generator



- Investigating solar power for long-term, sustainable energy



- Private firm to install and operate solar atop capped landfill (SVE) and at GWTP
- Air Force to purchase power through Power Purchase Agreement


Right Sizing Groundwater Treatment



- Implemented performance-based contract at former Davis Global Communication Site for groundwater cleanup
 - Existing pump and treat system replaced with sustainable in-situ bioremediation (passive vegetable oil injection)
 - Cost to complete reduced by \$15,000,000, along with reduced energy usage and greenhouse gas production



Soil Vapor Extraction



Soil vapor is the gas in the spaces between soil particles underground.

Soil Vapor Extraction vacuums vapors below ground and treats them. The byproduct is harmless.

- ♦ **Originally 16 systems pulling from 26 well fields**

- More than 1.5 million pounds of VOC contamination removed to date
- Many plumes reduced to the point SVE systems no longer needed


- ♦ **Projected for 2011, 12 systems pulling from 8 well fields**



Right Sizing Soil Vapor Extraction




- Optimizing well locations and shutting down units
- Aggressively reducing carbon footprint
 - eliminating thermal treatment processes
 - eliminating granular activated carbon for end stream polishing
- Some plumes meeting de minimus and using direct discharge



Right Flow Soil Vapor Extraction



Optimize soil vapor treatment by modifying flow route through blower either pre- or post-carbon treatment



Right Flow Soil Vapor Extraction



- ❑ Post-treatment flow through blower in summer reduces heat exchanger water use
 - Saves 450,000 gallons of water per system per year
 - Maintains optimal carbon adsorption



Fuels Bioventing



□ In-Situ treatment of fuel contamination

- Low carbon footprint
 - Small blower
- Avoids excavation, transportation, and landfill disposal
- Uses less energy than thermal desorption



Soil Remediation



AFCEE Sustainable Remediation Tool Model

- Alternatives analysis in feasibility study phase for more than 200 sites
 - Greenhouse gas generation and energy consumption
 - Off-site disposal vs. on-site consolidation of contaminated soil
- Habitat impact in sensitive habitats
 - Excavate of contaminants vs. leave in place



Questions?



Contact Information:

Mr. Steve Mayer, AFRPA

phone: 916-643-0830 ext. 224

email: Steven.Mayer@us.af.mil

